TOWN OF HADDAM, INLAND WETLANDS COMVISSION PERMIT APPLICATION Permit # (6-2)-603 Assessor's Map: 43 Lot: 19 Applicant's Name: 🖯 Home Phone: Work Phone: (860) 423-1233 Å Cell Phone: EMAIL: Address: Property Owner(s): Property Owners(s) Address: #/5/ GANUM, CT. 06441 Property Street Location OF WORK: Proposed Activity: SE/ECTIVE DIMENSIONS OF THE PROJECT STELM TIEST MINAGE CROSSINGS Type of upland review area (minor, major, watercourse) 28,4 Acres Total acreage of property where activity is proposed Total regulated area on the property (wetlands, watercourses) Size of regulated area on which regulated activity is to take place Acreage or square feet of wetlands and watercourses created Acres Acreage or square feet of wetlands and watercourses altered Acres Linear feet of stream alteration Ft Is property located within a Special Flood Hazard Area? Is the property located within a FEMA Flood Zone? Is property located within the Channel Encroachment Line of the Connecticut River?

NOTE: IF YOU HAVE ANY QUESTIONS ABOUT COMPLETING THIS APPLICATION, PLEASE
CALL THE HADDAM INLAND WETLANDS AGENT at (860) 345-8532 EXT 224

(over - to reverse side - both sides must be completed)

## EXHIBIT "A" CLEGG PROPERTY CUTTING SCHEDULE / SEDIMENTATION AND EROSION CONTROL PLAN

Scotland Hardwoods, LLC (A Rossi Company) plans to conduct a logging operation on approximately 28 of 28.4 total acres of land owned by Dale and Melody Clegg. This property is located off Pokorny Road in Haddam, Ct.. This land is further identified by the Haddam Assessors Map #43, Lot #19. A one to three man logging crew operating a log skidder will cut and skid the logs to one main yarding area. From this yarding area a tri-axle log truck will pick up the logs and exit the property via Pokorny Road. Regular working hours are from 7:00 AM to 5:00 PM Monday thru Friday and 8:00 AM to 4:00 PM on Saturdays. The property boundaries have been marked with fluorescent pink flagging and the main skid roads have been identified with blue. It is important to note that all of the main skid roads, yarding area and drainage crossings are already established as a result of a previous harvest that was conducted on the property about four years ago. Before the harvest starts all trees to be harvested will be marked with blue paint about 4 feet above the ground and at the base of each stump. It is estimated that about eighty thousand board feet of sawtimber will be removed from the property which involves about 23 total truck loads of logs. Concerning the harvest area, approximately 70% of the trees 14 inches D.B.H. (diameter at breast height) and larger, will be removed from the property. Red, Black and White Oak, Tulip Poplar, Black Birch and Hickory represent the species of trees involved with the harvest. All tops concerning the harvested trees, not be removed from the property, will be reduced to within five feet of the ground level. It is estimated that about four to six weeks will be required to complete the project. We hope to start the harvest during the late spring or early summer of 2022.

Three drainages will have to be crossed concerning the harvest. It is planned to use portable bridges, wood poles and or brush mats concerning all of the crossings. An anti-tracking pad will be maintained at the entrance to the yarding area to reduce dirt / mud being tracked onto the roadway. Upon completion of the harvest waterbars will be installed where necessary on the main skid roads. For further details concerning this activity please refer to Exhibit "B".

Sincerely yours,

SCOTLAND HARDWOODS

(A ROSSI COMPANY)

Rod Burgess

Ct. Certified Forester

